


versatile™ 4C Mailbox, 4C13D-13



This Product Distributed By:

U.S. Mail Supply, Inc.

3065 North 124th Street

Brookfield, WI 53005-3857

Ph: 800-571-0147 / Fax: 800-589-1068

www.usmailsupply.com

COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB1	3\" H x 12\" W x 15\" D	13
OUTGOING MAIL	OM2	6-1/2\" H x 12\" W x 15\" D	1
PARCEL	PL5	17\" H x 12\" W x 15\" D	1
PARCEL	PL6	20-1/2\" H x 12\" W x 15\" D	1

Notes:

- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - At least one customer compartment shall be positioned less than 48\" AFF.
 - No parcel locker (interior bottom shelf) shall be positioned less than 15\" AFF.
 - No patron (tenant) lock shall be positioned more than 67\" AFF.
 - No customer compartment (interior bottom shelf) shall be positioned less than 28\" AFF.
 - The USPS Arrow lock shall be positioned 36\"- 48\" AFF.
- This 4C mailbox can also be used for private applications.
- The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1 1/8\".

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

AF FLORENCE
manufacturing company

5935 Corporate Drive • Manhattan, KS 66503

www.florencemailboxes.com • (800) 275-1747

A GIBRALTAR INDUSTRIES COMPANY

MODEL 4C13D-13	REV C
SCALE NONE	LAST REV DATE 5/16-2014
DRAWING NUMBER 4C13D-13CS	DRAWN BY AFD