
versatile™ 4C Mailbox, 4CADS-03



This Product Distributed By: U.S. Mail Supply, Inc.

> 3065 North 124th Street Brookfield, WI 53005-3857 Ph: 800-571-0147 / Fax: 800-589-1068 www.usmailsupply.com

DESCRIPTION	COMPARTMENT	NT COMPARTMENT SIZE		
MAILBOX MB1		3" H x 12" W x 15" D	3	
OUTGOING MAIL	OM2	6-1/2" H x 12" W x 15" D	1	
PARCEL	PL5	17" H x 12" W x 15" D	1	

COMPARTMENT CHART

Notes:

- 1. This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
 - a. At least one customer compartment shall be positioned less then 48" above finished floor (AFF).
 - b. No parcel locker (interior bottom shelf) shall be positioned less than 15" AFF.
 - c. No patron (tenant) lock shall be positioned more than 67" AFF.
 - d. No customer compartment (interior bottom shelf) shall be positioned less than 28" AFF.
 - e. The USPS Arrow lock shall be positioned 36"- 48" AFF.
- 2. This 4C mailbox can also be used for private applications.
- 3. The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) 11/4".

PRODUCT SERIES: VERSATILETM 4C FRONT LOAD MAILBOX



5935 Corporate Drive • Manhattan, KS 66503 www.florencemailboxes.com • (800) 275-174 A GIBRALTAR INDUSTRIES COMPANY

	MODEL 4	CADS-03	REV	В
,	SCALE NONE		LAST REV DATE 5/15/2014	
3 1 <i>7</i>	DRAWING 4C/	NUMBER ADS-03CS		SDH