


# versatile™ 4C Mailbox, 4C14D-14



COMPARTMENT CHART

DESCRIPTION	COMPARTMENT	COMPARTMENT SIZE	QTY.
MAILBOX	MB1	3\" H x 12\" W x 15\" D	14
OUTGOING MAIL	OM2	6-1/2\" H x 12\" W x 15\" D	1
PARCEL	PL6	20-1/2\" H x 12\" W x 15\" D	2

**Notes:**

- This module meets the USPS STD-4C requirements for installation defined below when the mailbox is installed per the dimensions provided on this drawing.
  - At least one customer compartment shall be positioned less than 48\" AFF.
  - No parcel locker (interior bottom shelf) shall be positioned less than 15\" AFF.
  - No patron (tenant) lock shall be positioned more than 67\" AFF.
  - No customer compartment (interior bottom shelf) shall be positioned less than 28\" AFF.
  - The USPS Arrow lock shall be positioned 36\"- 48\" AFF.
- This 4C mailbox can also be used for private applications.
- The rough opening width for multi-unit 4C installations = (the sum of all actual unit widths) - 1/8\".

PRODUCT SERIES: VERSATILE™ 4C FRONT LOAD MAILBOX

**AF FLORENCE**  
manufacturing company  
5935 Corporate Drive • Manhattan, KS 66503  
www.florencemailboxes.com • (800) 275-1747  
A GIBRALTAR INDUSTRIES COMPANY

MODEL	4C14D-14	REV	A
SCALE	NONE	LAST REV DATE	5/10/2014
DRAWING NUMBER	4C14D-14CS	DRAWN BY	AFD